Friday, 01/02/2008 8:56:55 AM

User:

Linda Lacelle

**Process Sheet** 

Customer Job Number : CU-DAR001 Dart Helicopters Services

S.O. No. :

: 37136

**Estimate Number** 

.. 178

: 13150

P.O. Number

: 01/02/2008

This Issue

: NC

Prsht Rev. : 11 First Issue

Previous Run

Written By

Comment

Checked & Approved By

: Est Rev:A

08-01-30 new issue DD verifyed by:

Type

: SMALL /MED FAB

**Drawing Revision** Material

**Due Date** 

**Description:** 

6061-T6 .080 Sheet

FLOW WATER JET

**Drawing Name** 

Part Number

**Drawing Number** 

**Project Number** 

: U/R

: D37021

: 08/02/2008

: FORWARD DOUBLER

Qty:

2 Um:

Each

**Additional Product** 

Job Number:



Seq. #:

1.0

**Machine Or Operation:** 

M6061T6S080

Comment: Qty.: 0.5837 sf(s)/Unit Total: 1.1674 sf(s)

6061T6 aluminium sheet .080" thick

(M6061T6S080)

Batch: (06.330)

2.0



Comment: FLOW WATER JET


1-Cut as per Dwg D3702

Dwg Rev:\_ u Prog Rev:

2- Deburr if necessary

3.0

QC2



ser probable

Comment: INSPECT PARTS AS THEY COME OFF MACHINE

4.0

QC8

SECOND CHECK



Comment: SECOND CHECK

5.0

SMALL FAB 1

SMALL & MEDIUM FAB RESOURCE 1





Comment: SMALL & MEDIUM FAB RESOURCE 1

1- Deburr if necessary



Date: Friday, 01/02/2008 8:56:55 AM User: Linda Lacelle Customer: CU-DAR001 Dart Helicopters Services

**Process Sheet** 

**Drawing Name: FORWARD DOUBLER** 

Job Number: 37136 Part Number: D37021

Job Number:



Seq. #: 6.0

9.0

**Machine Or Operation:** Description:

INSPECT WORK TO CURRENT STEP QC5 **GINEERING** 

**PROVAL** Comment: INSPECT WORK TO CURRENT STEP

7.0 HAND FINISHING1

HAND FINISHING RESOURCE #1

Comment: HAND FINISHING RESOURCE #1 Chemical Conversion Coat as per QSI 005 4.1

8.0 QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION

Comment: INSPECT POWDER COAT/CHEMICAL CONVERSION

PACKAGING RESOURCE #1 PACKAGING 1

Dan Stow

Comment: PACKAGING RESOURCE #1 Identify and Stock

Location:

FINAL INSPECTION/W/O RELEASE 10.0 QC21

Comment: FINAL INSPECTION/W/O RELEASE

Job Completion

FOR ENGINEERING USE ONLY

06 (2018°C

## PROTOTYPE REQUEST FORM

**DART Aerospace Ltd.** 

CERTIFICATE OF CONFORMITY REQUIRED

9	roduct	#:	D412-	761
---	--------	----	-------	-----

Job #: 00224A


Product Name: VERTICAL REFERENCE DOOR

Requested By: MB

Date: 08.01.31

Design Manager Approva

Quantity	Part Number	Description	Drawing Date	Material Cert Req'd?	Due Date	Comments	Date Completed
2	D3700-1	INBOARD WINDOW DOUBLER	08.01.29	YES	ASAP	SEE BELOW	
2	D3700-3	OUTBOARD WINDOW DOUBLER	08.01.29	YES	ASAP	SEE BELOW	
2	D3701-1F	(FLOOR DOUBLER) FLAT PATTERN	08.01.29	YES	ASAP	SEE BELOW	2
2	D3702-1	FORWARD DOUBLER	08.01.30	YES	ASAP	MAKE ONE WITH HOLES/SLOT + ONE WITHOUT HOLES/SLOT + SEE BELOW.	1
2	D3703-1	AFT DOUBLER	08.01.30	YES	ASAP	SEE BELOW	
	,						
						HAND ALL W/Os AND PARTS TO DAN STOW	



С С **D3702-1 FORWARD DOUBLER** NEW ISSUE 08.01.30 NOTES:

1) MATERIAL: 6061-T6 (OR 6061-T62) ALUMINUM SHEET, 0.080 THICK PER AMS-QQ-A-250/11 OR AMS 4025 OR AMS 4027 (REF. DART SPEC. M6061T6S.080)

2) FINISH: CHEMICAL CONVERSION COAT PER DART QSI 005 4.1

3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED

4) UNITS: INCHES UNLESS OTHERWISE NOTED

5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX REV. DESCRIPTION DATE DESIGN **DART AEROSPACE LTD** DRAWN HAWKESBURY, ONTARIO, CANADA DRAWING NO. CHECKED REV. A D3702 MFG. APPR. SHEET 1 OF 2 APPROVED TITLE SCALE 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX FORWARD DOUBLER DE APPR. 2:3 6) IDENTIFICATION: N/A COPYRIGHT © 2008 BY DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS
NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT 7) WEIGHT: 0.21 lbs DATE 08.01.30

DART AEROSPACE LTD	Work Order:	37136	
Description: FORWIRD DOUBLER	Part Number:	D3702-1	
Inspection Dwg: 0 370) ~ (Rev: U/L		Page 1 of 1	

## FIRST ARTICLE INSPECTION CHECKLIST

X	First Article	Prototype
	· not same to	,,,o.o.,,po

Drawing Dimension	Tolerance	Actual Dimension	Accept	Rejec	Method of Inspection	
13.85	4/2.030	13.85	*			
13,37	4/030	13.37	8			
4.49	7/- ,030	4.49	Y			
0,125	4/ .010	* 198	20		į	
J66.P	4/ -010	9.714	A			,
9,948	4/ 1010	$\sim 100$	<i>&gt;</i> ∞			
				·		
	27			_		
			<del>-,</del>			·
					ļ	
				ļ		
				-		
			<del></del>	ļ		
				ļ		
				ļ	-	
				<u> </u>		
			· · · · · · · · · · · · · · · · · · ·			
						,
						·
		<del></del>				
					·	

Measured by:	Audited by:	Prototype Approval:	h
)-6-8 :e3eC	Date:	Date: C	18-02,07

Rev Date	Change		Revised by	Approved
A	New Issue	·	KJ/JLM	